BYNERGEX
CONSULTING



Registration pack · City of Cape Town

SSEG Registration Pack

A document checklist, an 11-step tracker and a pre-commissioning self-check for getting a solar PV or battery system authorised in Cape Town.

Bynergex Consulting
SSEG commissioning and sign-off, Cape Town

bynergex.com
+27 66 252 2655

Does your system need to be authorised?

If your property is supplied by the City of Cape Town and any of these apply, the answer is yes.

- [ ] You have, or plan, rooftop or ground-mounted solar PV connected to your electrical installation
- [ ] You have a hybrid inverter or battery system, even one that never exports (since 1 October 2023 the City treats all new PV and battery systems as grid-tied)
- [ ] You have a generator that can run alongside the grid
- [ ] You have a solar PV geyser (authorised online, without an engineer's sign-off)

> **Supplied by Eskom?**
>
> If Eskom supplies your property directly, you apply to Eskom for consent to connect, not to the City. The checklists in this pack are still a useful guide to what the utility will ask for.

Document and information checklist

- [ ] City e-Services profile, with Energy Services activated
- [ ] Inverter make and model, confirmed on the City's approved inverter list *before* purchase
- [ ] System details: PV array size (kWp), inverter rating (kVA), battery capacity (kWh), single or three phase
- [ ] Whether the system will export to the grid, or block reverse power
- [ ] Single-line diagram of the system as it will be installed
- [ ] Registered electrical contractor, registered on the City's Service Provider Registration
- [ ] ECSA-registered professional for commissioning sign-off, also registered with the City
- [ ] Proxy authorisation for your installer, if they're applying on your behalf
- [ ] Certificate of Compliance for the installation (after installation)
- [ ] Signed Supplemental Contract (after installation)
- [ ] For feed-in: The City's metering quotation for the AMI meter, paid

The 11-step tracker

Fill in the date and any reference number as you complete each step. Keep this page with your property records.

#	Step	Date done	Reference / notes
1	Register or log in on the City's e-Services portal		
2	Activate Energy Services in your profile		
3	Open Energy Services Applications		
4	Electrician and ECSA-registered professional complete Service Provider Registration		
5	Grant proxy authorisation to the installer (optional)		
6	Submit the SSEG application with the system's technical details		
7	Receive the Permission to Install letter by email		
8	Install the system, and leave it switched off		
9	Upload the Certificate of Compliance and signed Supplemental Contract		
10	ECSA-registered professional tests and signs off the commissioning report		
11	Receive the Commissioning Letter. Only now may the system be switched on		

The rule people break most

The Permission to Install letter lets you install. It does not let you switch on. Running the system before the Commissioning Letter arrives is a contravention in its own right.

Pre-commissioning self-check

Run through this with your installer before booking the commissioning visit. Each unticked item is a likely reason for a failed or delayed sign-off.

Matches the application

- [ ] Inverter make, model and rating are exactly as on the approved application
- [ ] PV array size, battery capacity and phase arrangement are as applied for
- [ ] Export or non-export setting matches the application

Safety and protection

- [ ] The inverter disconnects when the grid supply is switched off (loss of mains)
- [ ] Reverse power blocking or export limiting works, where the system doesn't export
- [ ] AC and DC isolators are installed, accessible and labelled
- [ ] Earthing and bonding are complete on the PV array, mounting and inverter
- [ ] Backup and changeover wiring on hybrid systems is correct and labelled

Labels and paperwork

- [ ] Warning labels at the main board and meter show that an embedded generator is installed
- [ ] Emergency shutdown procedure is displayed near the inverter
- [ ] As-built single-line diagram is on site
- [ ] Certificate of Compliance issued and uploaded
- [ ] System is still switched off

Need the system commissioned and signed off?

Bramwill Bruinders is an ECSA-registered Pr. Tech. Eng., and his SSEG sign-off is accepted by the City of Cape Town. We commission systems installed by others, and if something isn't ready, you get a plain list of what to fix.

bynergex.com/sseg-commissioning · consultant@bynergex.com · +27 66 252 2655

Based on the City of Cape Town's published SSEG process, checked in October 2026. Requirements change; confirm the current process on the City's website. This pack gives general guidance and is not a commissioning report. © 2026 Bynergex Consulting (Pty) Ltd.